

Annexure- I

Name of Work: "Internal campus road of cement blocks along with approach road from G.T. Road".

Sl. No.	Description of Items	Quantity	Unit
1	CONCRETE WORK		
1.1	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level :		
1.1.1	1:5:10 (1 cement : 5 coarse sand : 10 graded stone aggregate 40 mm nominal size).	40	Cum.
2	REINFORCED CEMENT CONCRETE		
2.1	Smooth finishing of the exposed surface of R.C.C. work with 6 mm thick cement mortar 1:3 (1 Cement : 3 fine sand).	130	Sqm.
3	ROAD WORK		
3.1	Cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 40 mm nominal size) in pavements, laid to required slope and camber in panels as required including consolidation finishing and tamping complete.	165	Cum.
3.2	Providing and laying 60 mm thick factory made cement concrete interlocking paver block of M -30 grade made by block making machine with strong vibratory compaction, of approved size, design & shape, laid in required colour and pattern over and including 50mm thick compacted bed of fine sand, filling the joints with fine sand etc. all complete as per the direction of Engineer-in-Charge.	1800	Sqm.
3.3	Cleaning of existing damaged road by brooming and collecting all rubbish, small stones, dirt etc. and stacking the same with in 50 metre lead all as per direction of the Engineer-in-Charge.	3400	Sqm.
3.4	Providing and fixing 100 mm wide, 6 mm thick AC sheet strip in expansion joints of C.C. road.	700	Metre